

- Ensure that moving parts are not in contact with stationary parts.
- Ensure that all main accident-prevention precautions have been taken (e.g. keeping ones distance from moving parts).
- Ensure that the impeller's rotation direction corresponds to the direction of rotation shown on the fan casing.
- Check all bolts within the first 500 hours of operation ensuring that they have been tightened to guarantee stability in assembled components.
- Verify that there are no operational abnormalities such as excessive vibrations or noise. In these instances it is necessary to stop the fan immediately.



comefri S.p.A.
MAGNANO IN RIVIERA (UD) - ITALY



TEL. 0432 - 798811

FAX. 0432 - 763378

TLX. 450098 COMEF I

Code number
Artikel Nr. N

V A1 18 970474 01

Serial number
Fabrik Nr. N

7 03072 05

Absorbed Power
Aufgen Leistung Pw (kW) max

146,19

Type
Typ

BCE 25/1800/2 LG

Project - Item
Projekt - Position

Operating Temperature
Betriebstemperatur t(°C) max

20

100

Operating Speed
Betriebsdrehzahl n (min⁻¹) max

767

Volume
Volumenstrom: (m³/s) Total Pressure ΔPt(Pa)
Gesamtdruck (Pa)

55,8

2076